

PBH WASHER

Product Information

Report of Structural Performance Testing of Wall Panels with PBH Washer.

For: Demand Products, Inc.
1055 Nine North Drive
Alpharetta, GA 30004
800-325-7540

By: Intertek Testing Services, NA Inc.
8431 Murphy Drive
Middleton, WI 53562
608-836-4400

Test Date: May 22 and 23, 2002

Report Date: May 23, 2002

Test Report #: 3025759

All services undertaken are subject to the following general policy: Reports are submitted for the exclusive use of the clients to whom they are addressed. Their significance is subject to the adequacy and representative character of the samples and to the comprehensiveness of the tests, examination or surveys made. No quotations from reports or use of Intertek Testing Services/Warnock Hersey's name, logo or mark is permitted except as expressly authorized by Intertek Testing Services in writing.

Test Report #3025759
ASTM E 330 Tests
Specimens: PBH Washer
Client: Demand Products, Inc.
Test Date: May 22 and 23, 2002

INTRODUCTION

This report gives the results of the evaluation of the provided samples (Job #3025759). The test results described in this report are limited to the submitted items.

On May 22 and 23, 2002 Intertek Testing Services NA, Inc. Middleton, WI conducted tests on 3 wall panels in accordance with ASTM E 330, (Test Method to determine the structural performance of exterior windows, curtain walls, and doors by uniform static air pressure difference), for Demand Products, Inc. of 1055 Nine North Drive, Alpharetta, GA.

Pressure measurements were taken with WHI Pressure transducer #553 with an accuracy of +/-1 PSF. Deflection measurements were taken with WHI linear transducers #438, 440, and 441 with an accuracy of +/- 0.002".

SPECIMEN DESCRIPTION

Structural Performance

Each test panel had overall dimensions of 51" wide by 96" high by 5³/₄" thick. The panels consisted of 18-gauge steel studs 16" o.c., 1/2" exterior grade drywall board, 6-mil poly sheet, 1 1/2" EPS foam, and a stucco finish system over the foam. The foam was attached to the studs with 2" diameter Demand Products PBH Washer and a 2 1/2" self-tapping screw. Two different fastening patterns were used and are described below.

Pattern A: PBH washers were placed near ends of each stud and 12" o.c. PBH washers bridged the joints in foam (36 fasteners/washers per 4' by 8' panel).

Pattern B: PBH washers were placed 4" from ends of each stud and 8" o.c. PBH washers did not bridge the joints in foam (48 fasteners/washers per 4' by 8' panel).

PROCEDURE

Structural Performance Tests

Conducted in accordance with ASTM E-330. Loads were applied in 10 PSF increments until failure. Deflection and set measurements were taken on the drywall board at top, center and bottom. Net deflection and set values were calculated by averaging end movement and subtracting from center movement.

continued ...

TEST RESULTS**Structural Performance**

Sample 1

Pattern A - 36 fasteners/washers per 4' by 8' panel

Load (PSF)	Net Deflection (IN)	Net Set (IN)
-10	0.067	0.007
-20	0.145	0.008
-30	0.227	0.004
-40	0.315	0.001
-50	0.412	0.005
-60	0.582	0.022
-70	0.625	0.009
-80	0.791	0.041
-90	1.350	0.319
-94	Studs buckled-sample would no longer sustain load	

Sample 2

Pattern B - 48 fasteners/washers per 4' by 8' panel

Load (PSF)	Net Deflection (IN)	Net Set (IN)
-10	0.064	0.002
-20	0.134	0.001
-30	0.215	0.003
-40	0.298	0.003
-50	0.387	0.006
-60	0.480	0.011
-70	0.580	0.012
-80	0.709	0.030
-90	0.878	0.055
-98	Studs buckled-sample would no longer sustain load	

Sample 3

Pattern B - 48 fasteners/washers per 4' by 8' panel

Load (PSF)	Net Deflection (IN)	Net Set (IN)
-10	0.056	0.002
-20	0.122	0.004
-30	0.192	0.003
-40	0.270	0.005
-50	0.352	0.006
-60	0.439	0.010
-70	0.525	0.010
-80	0.638	0.022
-90	0.778	0.047
-98	Studs buckled-sample would no longer sustain load	

CONCLUSIONS

The mode of failure for all three wall panels with Demand Products PBH Washer was studs buckling at the punch out location in the studs. The average ultimate negative load for all 3 walls tested per ASTM E-330 was -97 PSF.

Test Conducted by: Russ Burt
Engineering Technician

Report Reviewed by: Jim Turgeson
Project Manager-Fenestration